

Customer: 10' x 14' Pavilion
(12' x 16' - includes the 12" overhang)

Building Site, County:
Town, State:
Pavilion Size:
Estimate / Quote #:
Change Orders:
Contract Change Orders:
Drawing #:
Timber Species: Engineered
Connection Type: Timber Framed



1081 Salem Church Road
Middleburg, PA 17842

Sales Representative

Revision	Pack #	Quantity Required	U of M	Material Description	Print Description
Pavilion Engineered Timbers					
	Timber Framed	6	EACH	6X6X08 Lam S4S	Support posts
	Timber Framed	1	EACH	6X8X10 Lam S4S	Bottom Chord - Center
	Timber Framed	2	EACH	6X8X10 Lam S4S	Bottom Chord - Truss
	Timber Framed	2	EACH	6X8X16 Lam S4S	Headers
	Timber Framed	4	EACH	6X6X06 Lam S4S	Angle Braces (1=2) (Square / Arched)
	Timber Framed	2	EACH	6X6X04 Lam S4S	King Post - Truss
	Timber Framed	2	EACH	6X6X06 Lam S4S	Webb Members (1=2)
	Timber Framed	10	EACH	6X8X08 Lam S4S	Rafters
Roofing Materials					
		424	LF	1X8 T&G WP (WP4/WP18) (LF)	Exterior ceiling & soffit finish
		8	EACH	3/4" T&G OSB *	Roof Sheathing
		3	EACH	1-1/4" Coarse Drywall Screw 1#	Composite Roof (3/4" T&G OSB to 3/4" T&G ceiling)
		1	EACH	Rhino Roof Synthetic Felt (10sq.) 42"x286'	Roof felt paper
		8	EACH	Drip Edge Brown F55 (10' piece)	Aluminum drip edge
	SH	2	EACH	Shingle Starter 7.2"x33.5' Roll *	Shingle starters (30 LF / roll)
	SH	3	SQ.	30 YR Heritage Rustic Cedar Shingles *	30 yr Arch. Shingles (Verify Color Before Ordering)
	SH	1	EACH	Rustic Cedar Hip & Ridge Cap *	Ridge cap bundles (Verify Color Before Ordering)
Fasteners & Misc.					
		1	EACH	Dead Blow Hammer	Wood Peg Dead Blow Hammer
		1	EACH	1" Long Boy Drill Bit, 12" Length	Auger Drill Bit
	OP	38	EACH	8" x 1" Oak Pegs	8" Wood Pegs
		6	EACH	Post Anchor Brace, 6x6	6x6 Post Anchor Plates
		12	EACH	5/8 X 7 Galv. Bolt	Anchor Plate Galv. Bolts
		24	EACH	5/8 Galv. Washer	5/8 Galv. Washer
		12	EACH	5/8 Galv. Nut	Galv. Nut
		20	EACH	3/8 X 10 Lag	Rafter to Header Lags (2 per connection)
		6	EACH	3/8 X 10 Lag	Bottom Chord to Header Lags (1 per connection)
		4	EACH	3/8 X 10 Lag	Rafter to King Post Lags (2 per connection @ end trusses)
		12	EACH	3/8 X 12 Lag	Header to Post Lags (2 per connection)
		42	EACH	3/8 Washer	Washers
Preservative & Insecticide					
		1	EACH	Q8 5 Gal. - Medium Reddish Brown Premix (04)	Q8 Preservative - Natural (51), Light Gold (52), Medium Gold (53), Dark Brown (55), Barn Gray (56)
		1	EACH	NBS 30 Additive	Insect repellent (for Q8 preservative - 1 per 5 gallon)

Overall Total Retail Amount: **\$5,815.00**

Price includes materials, precutting, and prints. Shipping and sales tax are not included.

Roofing Materials					
		424	LF	1X8 T&G WP (WP4/WP18) (LF)	Exterior ceiling & soffit finish
		8	EACH	3/4" T&G OSB *	Roof Sheathing
		3	EACH	1-1/4" Coarse Drywall Screw 1#	Composite Roof (3/4" T&G OSB to 3/4" T&G ceiling)
		1	EACH	Rhino Roof Synthetic Felt (10sq.) 42"x286'	Roof felt paper
		8	EACH	Drip Edge Brown F55 (10' piece)	Aluminum drip edge
	SH	2	EACH	Shingle Starter 7.2"x33.5' Roll *	Shingle starters (30 LF / roll)
	SH	3	SQ.	30 YR Heritage Rustic Cedar Shingles *	30 yr Arch. Shingles (Verify Color Before Ordering)
	SH	1	EACH	Rustic Cedar Hip & Ridge Cap *	Ridge cap bundles (Verify Color Before Ordering)

Roofing Materials Overall Total Retail Amount: **\$1,300.00**